		ABS	TRACT OVE	ERALL QUO	TATION DI	ETAILS		
SI. NO	DESCRIPTION	1499/-	1749/-	1799/-	1999/-	2499/-	2999/-	3499/-
1.	STRUCTURE	Load Bearing up to Plinth level	Fully Framed Structure	Fully Framed Structure	Fully Framed Structure	Fully Framed Structure	Fully Framed Structure	Fully Framed Structure
2.	BRICK	Porotherm Bricks	Porotherm Bricks	Regular Chamber Bricks	Regular Chamber Bricks	Regular Chamber Bricks	Wire Cut Bricks	Wire Cut Bricks
3.	CONCRETE RATIO	M 20	M 20	M 20	M 20	M 20	M 20	M20
4.	CEMENT	Dalmia	Dalmia	Zuari, <mark>Priy</mark> a, Maha	Dalmia	Dalmia	Ultratech	Ultratech
5.	STEEL	JSW	JSW	GBR	JSW	JSW	JSW	JSW
6.	PLINTH HEIGHT	3 Feet	3 Feet	3 Feet	3 Feet	3 Feet	3 Feet	3 Feet
7.	SAND	M. Sand	M. Sand	M. Sand	M. Sand	M. Sand	M. Sand	M. Sand
8.	INTERIOR PLASTERING	Only On Structural Members and Opening Frames	Only On Structural Members and Opening Frames	Full Wall Area	Full Wall Area	Full Wall Area	Full Wall Area	Full Wall Area

We Build Your Dreams

9.	EXTERIOR PLASTERING	Only On Structural Members and Opening Frames as Per Elevation Requirement	Only On Structural Members and Opening Frames as Per Elevation Requirement	Full Wall Area	Full Wall Area	Full Wall Area	Full Wall Area	Full Wall Area
10.	HANDRAILS	S.S Handrails, Parapet Walls as Per Elevation Requirement	S.S Handrails, Parapet Walls as Per Elevation Requirement	Only Parapet Walls as Per Elevation Requirement	S.S Handrails, Parapet Walls as Per Elevation Requirement	S.S Handrails, Glass, Parapet Walls as Per Elevation Requirement	S.S Handrails, Glass, Parapet Walls as Per Elevation Requirement	S.S Handrails, Glass, Parapet Walls as Per Elevation Requirement
11.	ELECTRICAL WIRE	V. Guard / Hosper	V. Guard / Hosper	V. Guard / Hosper	V. Guard / Hosper	V. Guard / Hosper	V. Guard / Hosper	V. Guard / Hosper
12.	ELECTRICAL SWITCHES	Anc <mark>hor</mark> / Hosper	Anchor/ Hosper	Anchor / Hosper	An <mark>cho</mark> r / Hosper	Anchor/ Hosper	Anchor/ Hosper	Anchor/ Hosper
13.	PLUMBING	Avo <mark>npl</mark> ast / Ash <mark>irva</mark> d	Avonplast / Ashirvad	Avonplast / Astral	Avonplast / Ashirvad	Avonplast / Ashirvad	Avonplast / Ashirvad	Avonplast / Ashirvad
14.	WATER TANK	1000 L Aqua-Tech/ Sintex	1000 L Aqua-Tech/ Sintex	1000 L Aqua-Tech/ Sintex	1000 L Aqua-Tech/ Sintex	2000 L Aqua-Tech / Sintex	2000 L R.C.C / Brick	4000 L R.C.C / Brick
15.	WINDOW, DOOR FRAMES	Teak Wood	Teak Wood	Malaysian /// Teak Wood	Teak Wood	Teak Wood	Teak Wood	Teak Wood

16.	FLOORING	Granite, Ceramic Tiles, Athangudi Tiles Up to Rs 55	Granite, Ceramic Tiles, Athangudi Tiles Up to Rs 65	Ceramic Tiles Up to Rs 55	Granite, Ceramic Tiles, Athangudi Tiles Up to Rs 65	Granite, Ceramic Tiles, Athangudi Tiles Up to Rs 75	Granite, Ceramic Tiles, Athangudi Tiles Up to Rs 85	Granite, Ceramic Tiles, Athangudi Tiles Up to Rs 100
17.	KITCHEN WALL TILES up to 2' HEIGHT FROM COUNTER	Max. Up to Rs	Max. Up to Rs 35	Max. Up to Rs 35	Max. Up to Rs 35	Max. Up to Rs 45	Max. Up to Rs 50	Max. Up to Rs 60
18.	BATHROOM WALL TILES up to 7' HEIGHT	Max. Up to Rs	Max. Up to	Max. Up to Rs 25	Max. Up to Rs 35	Max. Up to Rs 45	Max. Up to Rs 50	Max. Up to Rs 60
19.	BATHROOM FLOORING	Max. Up to Rs	Max. Up to Rs 35	Max. Up to Rs 25	Max. Up to Rs 35	Max. Up to Rs 45	Max. Up to Rs 50	Max. Up to Rs 60
20.	BATHROOM DOOR	Max. Up to Rs 2500	Max. Up to Rs 3000	Max. Up to Rs 2500	Max. Up to Rs 3000	Max. Up to Rs 3000	Max. Up to Rs 4000	Max. Up to Rs 5000
21.	BATHROOM FIXTURES	Max. Up to Rs 8000 per Unit	Max. Up to Rs 10000 per Unit	Max. Up to Rs 7000 per Unit	Max. Up to Rs 10000 per Unit	Max. Up to Rs 15000 per Unit	Max. Up to Rs 20000 per Unit	Max. Up to Rs 25000 per Unit
22.	WALL PUTTY	Double Coat JK / Birla Wall Putty	Double Coat JK / Birla Wall Putty	Double Coat JK / Birla Wall Putty	Double Coat JK / Birla Wall Putty	Double Coat JK / Birla Wall Putty	Double Coat JK / Birla Wall Putty	Double Coat JK / Birla Wall Putty

23.	PAINTING	Clear Primer for Porotherm Brick as Per Consultant Suggestion	Clear Primer for Porotherm Brick as Per Consultant Suggestion	Asian paints for both Exterior and Interior				
24.	FALSE CEILING	-	-	-	-	-	Hall, Master Bedroom Max. 75 Per Sq. ft	Hall, Bedroom, Dinning Max. 75 Per Sq. ft
25.	MODULAR KITCHEN	Open Cuddapah Slabs	Open Cuddapah Slabs	Open Cuddapah Slabs	Open Cuddapah Slabs	PVC Modular Kitchen Unit	MDF / Plywood Modular Kitchen Unit	Teak Modular Kitchen Unit
26.	LOFT, CUPBOARDS	Open Cuddapah Slabs	Open Cuddapah Slabs	Open Cuddapah Slabs	Open Cuddapah Slabs	PVC Shutter's	MDF / Plywood Shutter's	Teak Shutter's
27.	BOREWELL	-		_		-	Up to 300 Feet Only	Up to 300 Feet Only
28.	SMOKELESS CHIMNEY	-	- (ID	BUILDI	ERS &	Havel's	Havel's
29.	RAINWATER HARVESTING	-	-	We-Build	PROMC		-	Done With Proper Geo- Technical Survey

30.							1 KV	5 KV
	SOLAR						Invertor with	Invertor with
	POWER	-	_	_	_	_	Solar Panel	Solar Panel
31.	CCTV	_	-	-	-	16 Channels 8 Cameras	16 Channels 10 Cameras	16 Channels 16 Cameras
32.	FRONT	Normal	Normal	Normal	Normal	Design	Design	Design
	ELEVATION	Mas <mark>onr</mark> y	Masonry	Masonry	Masonry	Expense Up	Expense Up	Expense Up
	COST	Wor <mark>ks O</mark> nly	W <mark>ork</mark> s Only	Works Only	Works Only	to 1 Lakhs	to 1.5 Lakhs	to 2.5 Lakhs
33.	LABOUR SHED	Client Scope	Client Scope	Client Scope	Contractor Scope	Contractor Scope	Contractor Scope	Contractor Scope

WORKS NOT INCLUDED IN THE ABOVE QUOTATION:

- **\$ E.B CONNECTION AND ELECTRIC BILL DURING CONSTRUCTION.**
- ❖ For 5 feet high compound wall Rs 1500 for 1 R. Ft.
- Septic tank Rs 1500<mark>0 fo</mark>r 1000 liters.
- **UG sump Rs 25000 for 1000 liters.**
- **All the final fixtures like fancy fitting, fan, led light, decorative lights come under client scope.**
- **Building plan approval & Tax fees are arranged and paid by client.**
- **Temporary EB connection should be arranged by client.**
- ***** Water facility should be arranged by client.
- **❖** In case of any alter works you should consult with Engineer.
- **❖** Work that is not stated in our quotation is considered to be under the client's scope.
- ***** Five terms of payment should be settled in a Specific time.

We Build Your Dreams

Ground Floor

	SCHEDULE OF PAYMENTS							
SI.NC)	DESCRIPTION	AMOUNT					
1.		At the Time of Signing the Construction Agreement 25%						
2.		At the Time of Completing Basement Work 25%						
3.		At the Time of Time of before roofing 25%						
4.		At the Time of Plastering Works 20%						
5.		At the Time of Painting Works 5%						

Ground and First Floor

			SCHEDULE OF PAYMENTS	
	SI.NO)	DESCRIPTION AMOUNT	•
	1.		At the Time of Signing the Construction Agreement 25%	
	2.		At the Time of Completing Basement Work 25%	
	3.		At the Time of Time of Ground Floor roofing 25%	
	4.		At the Time of First Floor roofing 20%	
	5.		At the Time of Painting Works 5%	
Ground , First	, Seco	on	d Floor	
			COMPANIA OF DAVIATION	۰

	SCHEDULE OF PAYMENTS	
SI.NO	DESCRIPTION	AMOUNT
1.	At the Time of Signing the Construction Agreement 15%	
2.	At the Time of Completing Basement Work 15%	
3.	At the Time of Time of Ground Floor roofing 15%	S &
4.	At the Time of Time of First Floor roofing 15%	
5.	At the Time of Time of Second Floor roofing 15%	EKS
6.	At the Time of Plastering Works 20%	
7.	At the Time of Painting Works 5% Dulla Tour Dream.	3